

10-3  
4-070063

To:

API Number: 15-163-20,893 -00-00

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

SE NE SW /4 SEC. 23, 08 S, 17 W  
1650 feet from S section line  
2970 feet from E section line

Operator license# 5145

Lease: Schindler "B" Well # 5

Operator: Dreiling Oil, Inc.

County: Rooks 11A.45

Address: Box 550 - 1008 Cody Ave.  
Hays, Kansas 67601

Well total depth 3460 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 1/2 Inch @ 168 feet  
W/135 sxs.

ABAND. oil well , Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD. \_\_\_\_\_, D&A \_\_\_\_\_

Plugging contractor: Dreiling Oil, Inc. License# 5145

Address: P.O. Box 550 - Hays, Kansas 67601

Company to plug at: Hour: 10:00 A.M. Day: 03 Month: October Year: 1997

Plugging proposal received from: Ivan Edsall

Company: Dreiling Oil, Inc. Phone: 785-625-8327

Were: Perforate at 1750' - 1300' - 825'. PBT 3404'. 4 1/2" casing at 3459'.  
Fill casing to surface with cement.  
Ordered 265 sxs 60/40 pozmix - 10% gel with 500 sxs hulls.  
Dakota 496' - 796'. Anhy. 1286' - 1306'. Salt 1611' - 1711'.

Vertical stamp: RECEIVED  
OCT 23 1997  
10:28

Plugging Proposal Received by: Rich Williams 10-14-97  
Plugging operations attended by agent? All , Part [ ], None [ ]

Completed: Hour: 11:00 A.M., Day: 03, Month: October, Year: 1997

Actual plugging report: LK perforated at 1750' - 1300' - 825'. Allied pumped 50 sxs with 100# hulls down backside. Max. P.S.I. 100#. S.I.P. 100#. Pumped 215 sxs with 400# hulls. Max. P.S.I. 500#. Shut in - slight vacuum.

Remarks:

Condition of casing(in hole): GOOD  BAD \_\_\_\_\_  
Bottom plug(in place): YES , CALC \_\_\_\_\_, NO \_\_\_\_\_  
Plugged through TUBING \_\_\_\_\_, CASING .  
Anhy.plug: YES  NO \_\_\_\_\_  
Dakota plug: YES , NO \_\_\_\_\_  
Elevation: 1971 GL

I [ ] did not [ ] observe the plugging.

Richard Williams  
(agent)

INVOICED

DATE OCT 23 1997

INV. NO. 49265