

4-100535

TO:

9-11

API number: 15-163-23,305-00-00

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, ROOM #2078
WICHITA, KANSAS 67202-3802

C W2 W2 NW /4 SEC: 23-08-17W
3960 Feet from S (N/S) Line
4950 Feet from E (E/W) Line

Operator License# 30730

LEASE: Chesney K-P WELL # 1

Operator: Horizontal Devel. & Prod., Inc.

County: ROOKS 110,96

Address: P.O. Box 12728
Dalas, Texas 75225

Well total Dept 3408 feet
Conductor Pipe inch @ feet
Surface pipe 8 5/8 inch @ 237 feet

Aband. Oil Wel Gas Well Input Well SWD: D & A: X

Plugging contractor: VonFeldt Drilling, Inc. License#: 09431

Address: Russell, Kansas

Company to plug at: Hour: Day: Month: Year:

Plugging proposal received from Bill Alm

Company: VonFeldt Drilling, Inc. Phone:

Were:

1st plug @ 1325' with 25 sx
2nd plug @ 760' with 100 sx
3rd plug @ 280 with 40 sx
4th plug @ 40' with wiper plug and 10sx
Rat hole - 15 sx

Plugging proposal received by: David Wann

Pluggings operations attended by agent? All [], Part [], None [X]

Completed Hour: 8:30 pm Day: 11 Month: September Year: 1998

Actual plugging report:

Hole plugged as above. Order 190 sacks of 60/40 Posmix w/6% gel and 1/4 lb flowcell per sack

Remarks: Elevation: 1936 GL, Anhydrite top: 1324 feet Anhy. plug: Y 9-21-98

Dakota plug: Y Bottom plug in place N

Plugged through drill pipe Y

Arbuckle top Cemented by: Allied Cementing

I did [] did NOT [X] observe the plugging.

David Wann (agent)

P.I.R.T. III

INVOICED

DATE SEP 23 1998

INV. NO. 51351

JAN 29 1999 9-11