

8-18

4-070054

API Number: 15-163-20,994 -0000

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

SE NW NW /4 SEC. 20, 08 S, 17 W  
4290 feet from S section line  
4290 feet from E section line

Operator license# 31013

Lease: Stamper Well # A-1

Operator: The Don Brown Company

County: Rooks 109.43

Address: P.O. Box 24  
Plainville, Kansas 67663

Well total depth 3367 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 168 feet  
W/120 sxs.

ABAND. oil well X, Gas well, Input well, SWD., D&A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 11:00 A.M. Day: 18 Month: August Year: 1997

Plugging proposal received from: Don Brown

Company: Don Brown Company Phone:

Were: 4 1/2" casing set at 3369' with 130 sxs.  
Ordered 275 sxs. 60/40 pozmix - 10% gel with 800# hulls.  
Dakota 413' - 663' - Anhy. 1232' - 1257' - Salt 1557' - 1657'.  
Perfs 3067' - 3340'. Perforated 1700' - 1250' - 675'.

Vertical stamp: RECEIVED  
AUG 20 1997  
STATE CORPORATION COMMISSION  
WICHITA, KANSAS

Plugging Proposal Received by: Richard Williams 8-20-97

Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 2:00 P.M., Day: 18, Month: August, Year: 1997

Actual plugging report: LK Wireline perforated 1700' salt - 1250' anhy. - 675' Dakota - fluid level 1500'. Ran 70 joints 2 3/8" tubing 2170'. Allied mixed 110 sxs. 60/40 pozmix - 10% gel with 400# hulls. Max. P.S.I. 400#. Shut down slight vacuum. Pulled tubing out and pumped 65 sxs. 60/40 pozmix - 10% gel with 200# hulls down 4 1/2" casing. Max. P.S.I. 1000#. S.I.P. 400#. Hooked on backside 4 1/2" - pumped 50 sxs. with 100# hulls. S.I.P. 100#.

Remarks: Allied Cementing. Dakota broke in - less than one barrel of fluid daily.

Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO  
Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO  
Plugged through TUBING X, CASING X Elevation: 1888 GL

I did [ X ] / did not [ ] observe the plugging.

Richard Williams  
(agent)

Form CP-2/3

INVOICED

DATE 8-20-97

INV. NO. 48825

Handwritten mark: (D)