

6 041289

15-1634-9-297-00-01 *Dim 366*
API NUMBER 15- D-23, 325

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

N₂SWSW N₂W₂ SEC. 20, T 8 S, R 17 W/EX

3170 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5635
Operator: The Gene Brown Co.
Name & Address: Drawer 220
Plainville, Ks. 67665

Lease Name Stamper A Well # 5
County Rooks 115.27
Well Total Depth 3547 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 211 w/135 sks

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well x D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Cementing License Number _____

Address Hays, Ks.

Company to plug at: Hour: 8:00 AM Day: 9 Month: April Year: 19 91

Plugging proposal received from Tom Brown

(company name) Gene Brown Co. (phone) _____

were: 5 1/2 casing set at 3369 w/130 sks cement: O.H. to 3547;

Perf at 1250 circ w/650 sks cement. Ordered 250 sks 65/35 poz 8% gel w/1/4 lb

STATE CORPORATION COMMISSION f.c. plus 5 sks hulls plus 100 sks common w/1/4 lb f.c.

RECEIVED

APR 26 1991

4/26/91

CONSERVATION DIVISION
Wichita, Kansas
Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All x Part _____ None _____

Operations Completed: Hour: 9:30AM Day: 9 Month: April Year: 19 91

ACTUAL PLUGGING REPORT Pumped in 5 1/2 casing w/100 sks cement w/1/4 lb
f.c. plus pumped in add 150 sks cement w/1/4 lb f.c. and 5 sks hulls mixed in
cement. Max 1150 lbs. S.I. 300 lbs. Cement at surf in annulus.

Remarks: _____
additional description is necessary, use BACK of this form.)

INVOICED

I (did / ~~xxxxxx~~) observe this plugging.

DATE 5-13-91

INV. NO. 31803

Gil S.

Signed Dennis L. Hamel
(TECHNICIAN)
Dennis L. Hamel