

4-041478

6-25

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-163-20,364-00-00

NE NW NW /4 SEC. 20, 08 S, 17 W
4950 feet from S section line
4290 feet from E section line

Operator license# 5635

Lease Stamper well # 1-V

Operator: Gene Brown Company

County Rooks

Address: Drawer 220
Plainville, Kansas 67663

Well total depth 3322 feet ^{107.96}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 249 feet
w/200 sx.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License#

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00A.M. Day: 25 Month: June Year: 93

Plugging proposal received from: Tom Brown

Company: Gene Brown Company Phone:

Were: 5 1/2" casing set @ 3321' w/175 sx. cement. Perf. @ 3044'-3328'.
Salt @ 2050' - Anhy. @ 1250' - Dakota @ 715'.
Ordered 225 sxs. 60/40 pozmix - 10% gel. with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 12:30P.M. Day: 25, Month: June, Year: 93

Actual plugging report: R.I.H. with tubing to 2400'. Spot 65 sx. cement
w/200# hulls, pull to 1400'. Spot 40 sx. cement w/100# hulls. Pull
to 700'. Spot 50 sx. w/100# hulls to circulate cement at surface.
Pull tubing, squeezed 45 sxs. cement w/50# hulls. Max. 300#. S.I. 100#.
Hooked-up to 8 5/8" S.P. Squeezed in 25 sx. cement w/500# hulls.
Max. 200#. S.I. 100#.

Remarks:

Condition of casing(in hole): GOOD BAD X Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING . Elevation: GL

I do not observe the plugging.

Dennis L. Hamel
CONSERVATION DIVISION
Wichita, Kansas

(agent)
Form CP-2/3 7-14-93

INVOICED
DATE 7-21-93
INV. NO. 38178
6-25

RECEIVED
STATE CORPORATION COMMISSION
JUL 14 1993