

15-163-19257-00-01

10-3

4-070064

E-24,104

API Number: 15- - 5-5-79

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

S2 SW SW /4 SEC. 23, 08 S, 17 W
330 feet from S section line
660 feet from E section line

Operator license# 5145

Lease: Schindler "B" Well # 6

Operator: Dreiling Oil, Inc.

County: Rooks 114.01

Address: Box 550 - 1008 Cody Ave.
Hays, Kansas 67601

Well total depth 3508 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 inch @ 170 feet
W/110 sxs.

ABAND. oil well, Gas well, Input well X, SWD., D&A

Plugging contractor: Dreiling Oil, Inc. License# 5145

Address: P.O. Box 550 - Hays, Kansas 67601

Company to plug at: Hour: 9:00 A.M. Day: 03 Month: October Year: 1997

Plugging proposal received from: Ivan Edsall

Company: Dreiling Oil, Inc. Phone: 785-625-8327

Were: Fill casing with cement to surface.
Ordered 300 sxs 60/40 pozmix - 10% gel with 500# hulls.
Squeezed 1765' - 1797' w/150 sxs. Squeezed 70 sxs at 725' - 797'.
Dakota 500' - 800'. Anhy. 1297' - 1317'. Salt 1622' - 1722'.

10-14-1997
10 22 20

Plugging Proposal Received by: Rich Williams
Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 10:00 A.M., Day: 03, Month: October, Year: 1997

Actual plugging report: Allied pumped 300 sxs 60/40 pozmix - 10% gel with 500# hulls.
Max. P.S.I. 1000#. S.I.P. 700#. Hooked-up to backside 8 5/8" pressured up to 500#. Cement in head.

Remarks:
Condition of casing(in hole): GOOD X BAD
Bottom plug(in place): YES X, CALC, NO
Plugged through TUBING, CASING X

Anhy.plug: YES X NO
Dakota plug: YES X NO
Elevation: 1980 GL

I did [X] / did not [] observe the plugging.

Richard Williams
(agent)

INVOICED

Form CP-2/3

DATE OCT 29 1997
INV. NO. 49264