

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01822-00-00
Spot: SWNENW Sec/Twnshp/Rge: 30-8S-17W
4290 feet from S Section Line, 3630 feet from E Section Line
Lease/Unit Name: BIRD Well Number: 4
County: ROOKS Total Vertical Depth: 3405 feet

Operator License No.: 5285
Op Name: HANSEN, DANE G. - TRUST
Address: PO BOX 187
LOGAN, KS 67646

Conductor Pipe: Size feet: 8/110.66
Surface Casing: Size 8.625 feet: 163 150 sxs
Production: Size 5.5 feet: 3393 125 sxs
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 04/24/2002 9:00 AM

Plug Co. License No.: 5285 Plug Co. Name: HANSEN, DANE G. - TRUST

Proposal Rcvd. from: RICHARD L. WALLGREN, S Company: HANSEN, DANE G. - TRUST Phone: (785) 689-4816

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 400# hulls.
D.V. Tool at 1307'.
Squeeze at 665' - 698' w/50 sxs.
Squeeze at 1150' - 1200' w/250 sxs.
Squeeze at 1169' - 1200' w/90 sxs.
Squeeze at 1150' - 1179' w/70 sxs.

Plugging Proposal Received By: JAY PFEIFER

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 04/24/2002 12:00 PM

KCC Agent: JAY PFEIFER

Actual Plugging Report:

Set CIBP at 3058'.
TIH with bit and got outside the pipe around 2600'.
Decided to P&A.
Tied onto 5 1/2" and pumped to pressure with 240 sxs cement with 400# hulls.
Annulus full of cement.

RECEIVED

APR 30 2002

KCC WICHITA

4302002

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Jay Pfeifer

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 5-01-02

INV. NO. 2002061723

APR 25 2002