

6010183

Mustang Drilling #8m

API NUMBER 15-163-22303-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW, SEC. 8, T. 8 S, R. 18 W
1650 feet from W/S section line

TECHNICIAN'S PLUGGING REPORT

330 feet from W/S section line
Lease Name Maddy Sweet North Well # 1

Operator License # 5652

County Rooks

Operator: Mustang Drilling
Name & Address Box 1425

Well Total Depth 3460 ^{112.45} feet

Wichita Ks.
Great Bend, Ks 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well (D&A)

Other well as hereinafter indicated _____

Plugging Contractor Union Drilg Co. License Number 5103

Address 422 Union Center Wichita Ks.

Company to plug at: Hour: 1 PM Day: 14 Month: 8 Year: 19 84

Plugging proposal received from Lyle Cason

(company name) Union Drilg. (phone) _____

were: order 210 sx. cement 50/50 permix 6% gel. 3% c.c.
1 sx hulls 1-8 5/8 plug 1 sx flow seal

Heavy mud between all plugs

Pump cement down drill pipe

Elev. 1954 Anhydrite 1343-72 Arbuckle 3446

Dakota 1475 Plugging Proposal Received by Dale Z Balthazor
479-780 (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ (Part) _____ None _____

Operations Completed: Hour: 5:30 PM Day: 14 Month: 8 Year: 19 84

ACTUAL PLUGGING REPORT circulated @ 3450 for 30 mi.

25 sx @ 3450

25 sx @ 1360

100 sx @ 780 mixed with 1 sx flow seal

40 sx @ 260 dumped 1 sx hulls pushed plug to 40'

10 sx @ 40

Remarks: 10 sx in Rat Hole. Cementing to Sun.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 8-29-84

INV. NO. 3429

RECEIVED
08-27-1984
AUG 27 1984

Signed Dale Z Balthazor
(TECHNICIAN)

8-24-84