

7-23

204  
R

4- 041410

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-163-20,035 -00-00

S2 N2 N2 /4 SEC. 30 , 08 S, 17 W  
4775 feet from S section line  
2640 feet from E section line

Operator license# 5285

Lease Bird well # 14

Operator: Dane G. Hansen Trust

County Rooks

Address: P.O. Box 187  
Logan, Kansas 67646

Well total depth 3409 feet <sup>110.79</sup>  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 185 feet  
w/135 sx.

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 10:00A.M Day: 23 Month: July Year: 92

Plugging proposal received from: Rich Walgren

Company: Dane G. Hansen Trust Phone: \_\_\_\_\_

Were: 4 1/2" casing set @ 3409' w/175 sx. cement. Perf. @ 3120' - 3318'. W.L.M. 3340'. Squeeze @ 2115' - 2486' w/500 sx. Squeeze @ 690' - 845' w/140 sx. Squeeze @ 690' - 720' and 815' - 845' w/50 sx. Ordered 350 sxs. 60/40 pozmix - 10% gel. with 1/4# F.C. plus 400# hulls.

Plugging Proposal Received by: Dennis L. Hamel  
Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 12:00P.M, Day: 23, Month: July, Year: 92

Actual plugging report: R.I.H. with tubing to 1330'. Pumped 150 sx. cement w/400# hulls in cement to circulate cement at surface. P.O.O.H. with tubing and squeezed additional 150 sx. cement down 4 1/2" casing. Max. P.S.I. 300#. S.I.P. 100#. Hooked-up to 8 5/8" S.P. Squeezed in 20 sx. cement down annulus space. Max. P.S.I. 300#. S.I.P. 300#.

16-592

RECEIVED  
STATE CORPORATION COMMISSION

Remarks: \_\_\_\_\_  
Condition of casing(in hole):GOOD  BAD \_\_\_\_\_ Anhy.plug: YES  NO OCT 5 1992  
Bottom plug(in place): YES \_\_\_\_\_, CALC , NO \_\_\_\_\_ Dakota plug: YES , NO \_\_\_\_\_  
Plugged through TUBING \_\_\_\_\_, CASING . Elevation: \_\_\_\_\_  
CONSERVATION DIVISION  
Wichita, Kansas

**INVOICED**

I did  (or) did not  observe the plugging.

Dennis L. Hamel

DATE 10-8-92

(agent)

REV. NO. 36382

Form CP-2/3