

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-179-20084-00-00

RECEIVED
STATE CORPORATION COMMISSION
APR 11 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name John O. Farmer, Incorporated,

Complete Address 370 West Wichita, Russell, Kansas.

Lease Name Bell Well No. 1

Location SW-SW-NE Sec. 20 Twp. 7 Rge. (E) (W) 29

County Sheridan Total Depth 4220'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 2:00 PM Day 6 Month 4 Year 1968

The above well was plugged as follows:

282'--8 5/8" Surface pipe, cement circulated with 160 Sx.
Top of Dakota Section @ 1400'.

Circulated hole with heavy mud. Pulled DP to 1625' and displaced 100 Sx. cement
thru DP from 1625' to 1300'. Pulled DP to 310' and displaced 20 Sx. cement thru DP
from 310' to 250'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Dichel
Well Plugging Supervisor

INVOICED

DATE 4/11/68
INV. NO. 2565-W