

KANSAS

44 STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 30 1968
CONSERVATION DIVISION
Wichita, Kansas
09-30-1968

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-179-20136-00-00

Operator's Full Name Braden Drilling, Incorporated & Zenith Drilling Corporation, Inc.,

Complete Address: 1620 Wichita Plaza Building, Wichita, Kansas.

Lease Name Westerman Well No. 1-36

Location NW NW NW 440' FNL & 440' FWL Sec. 36 Twp. 7 Rge. (E) (W) 30

County Sheridan Total Depth 4261

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Braden Drilling, Incorporated,

Address: 1620 Wichita Plaza Building, Wichita, Kans. License No. _____

Operation Completed: Hour 6:00PM Day 25 Month 9 Year 1968

The Above well was plugged as follows:

325'--8 5/8" Surface casing, cement circulated.
Top of Dakota section @ 1280'.

Circulated hole with heavy mud. Pulled DP to 1500' and displaced 100 Sx. cement thru
DP from 1500' to 1175'. Pulled DP to 300' and displaced 20 Sx. cement thru DP from
300' to 240'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: N. L. Dechale
Well Plugging Supervisor

INVOICED

DATE 9/30/68
INV. NO. 8540-W