

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-179-20241 00-00

01-15-1970  
RECEIVED  
STATE CORPORATION COMMISSION  
JAN 15 1970  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Messman-Rinehart Oil Company,

Complete Address 1432 Wichita Plaza Building, Wichita, Kansas.

Lease Name Hatfield Well No. 1

Location CW/2-NW-NW Sec. 22 Twp. 7 Rge. (E) (W) 29

County Sheridan Total Depth 4230'

Abandoned Oil Well          Gas Well          Input Well          SWD Well          D & A X

Other well as hereafter indicated         

Plugging Contractor Red Tiger Drilling Company,

Address 1720 Wichita Plaza Building, Wichita, Kansas. License No.         

Operation Completed: Hour 12:15 AM Day 14 Month 1 Year 1970

The above well was plugged as follows:

349'--8 5/8" Surface casing, cement circulated with 280 Sx.  
Top of Dakota section @ 1325'.

Circulated hole with heavy mud. Pulled DP to 1550' and displaced 100 Sx. cement thru  
DP from 1550' to 1225'. Pulled DP to 375' and displaced 25 Sx. cement thru DP. from  
375' to 300'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *A. L. Nichols*  
Well Plugging Supervisor

INVOICED  
DATE 1/15/70  
INV. NO. 1260-u