

Y
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-179-20019-00-00

03-25-1968
RECEIVED
STATE CORPORATION COMMISSION
MAR 25 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Dean & Clark, Incorporated,

Complete Address: 416 Union Center Building, Wichita, Kansas.

Lease Name Hesterberg Well No. 1

Location CNE-NE-NE Sec. 25 Twp. 7 Rge. (E) (W) 29

County Sherdian Total Depth 4220

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 6:30 PM Day 22 Month 3 Year 1968

The Above well was plugged as follows:

288'--8 5/8" Surface pipe, cement circulated with 200 Sx.
Top of Dakota @ 1700'.

Circulated hole with heavy mud. Pulled DP to 1920' and displaced 100 Sx. cement thru
DP from 1920' to 1600'. Pulled DP to 300' and displaced 20 Sx. cement thru DP from
300' to 240'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *M. L. Nichols*
Well Plugging Supervisor

DATE 3/26/68

INV. NO. 7464-11