

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 10 1971  
05-10-1971  
CONSERVATION DIVISION  
Wichita, Kansas

15-179-20250-00-00

Operator's Full Name Hummon Oil, Incorporated,  
Complete Address 821 Union National Building, Wichita, Kansas.  
Lease Name Pope Well No. 1  
Location SW-NW-NE Sec. 19 Twp. 7 Rge. (E) (W) 29  
County Sheridan Total Depth 4249'  
Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A         
Other well as hereafter indicated         
Plugging Contractor Knight Casing Pulling Company, Incorporated,  
Address Box #405, Chase, Kansas. License No. 624  
Operation Completed: Hour 5:00 PM Day 4 Month 5 Year 1971

The above well was plugged as follows:

287'--8 5/8" Surface casing, cement circulated.  
4249'--4 1/2" Production casing cemented on bottom with 150 Sx. Well plugged back to 4150'. Top perforations from 4070' to 4078'.  
Pushed plug to 4060', sanded back to 4050' and set 3 Sx. cement with dump bailer.  
Pulled 4 1/2" casing (2600') and squeezed well initially with 5 sacks hulls and 5 sacks gel and followed with 100 Sx. cement from 1625' to 1300' then 25 sacks gel from 1300' to 300' and followed with 25 Sx. cement from 300' to 225' then 5 sacks gel from 225' to 25' and finally 10 Sx. cement from 25' to bottom of cellar. Maximum pump-in pressure-200#. Final shut-in pressure-100#. (Mudding and cementing by Allied Cmtg. Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 5/13/71

INV. NO. 3688-W