

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
SEP 4 1968
CONSERVATION DIVISION
Wichita, Kansas
09-04-1968

15-179-20130-00-00

Operator's Full Name Imperial Oil Company,

Complete Address: 780 Fourth National Bank Building, Wichita, Kansas.

Lease Name Gilchrist Well No. 1

Location CNE-NE Sec. 21 Twp. 7 Rge. (E) (W) 30

County Sheridan Total Depth 4225

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 3:00 PM Day 2 Month 9 Year 1968

The Above well was plugged as follows:

348'--8 5/8" Surface pipe, cement circulated with 275 Sx.
Top of Dakota section @ 1500'.

Circulated hole with heavy mud. Pulled DP to 1710' and displaced 100 Sx. cement thru
DP from 1710' to 1390'. Pulled DP to 420' and displaced 20 Sx. cement thru DP from
420' to 355'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 9/4/68
INV. NO. 8409-w