

14
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-179-20193-00-00

RECEIVED
STATE CORPORATION COMMISSION
APR 3 1969
CONSERVATION DIVISION
Wichita, Kansas
04-03-1969

Operator's Full Name Dreiling and Hiko Bell Mining & Oil Company,

Complete Address: R. R. #2, Victoria, Kansas.

Lease Name Conn Well No. 1

Location SW-SW-SE Sec. 34 Twp. 7 Rge. (E) (W) 30

County Sheridan Total Depth 4300

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: L. J. Dreiling & Sons, Incorporated,

Address: R. R. #2, Victoria, Kansas. License No.

Operation Completed: Hour 2:00 PM Day 30 Month 3 Year 1969

The Above well was plugged as follows:

349'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1450'.

Circulated hole with heavy mud. Pulled DP to 1675' and displaced 100 Sx. cement thru
DP from 1675' to 1350'. Pulled DP to 375' and displaced 20 Sx. cement thru DP from
375' to 315'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. S. Nichols
Well Plugging Supervisor

DATE 4/3/69
INV. NO. 9542-W