

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-179-2061-00-00

RECEIVED
STATE CORPORATION COMMISSION
NOV 25 1968
CONSERVATION DIVISION
Wichita, Kansas
11-25-1968

Operator's Full Name Petroleum, Incorporated,

Complete Address: 300 West Douglas, Wichita, Kansas.

Lease Name Huffer Well No. 1

Location App: -NE-NE-NW, Sec. 24 Twp. 7 Rge. (E) (W) 30

County Sheridan Total Depth 4245'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Garvey Drilling Company,

Address: Rte. #2, Great Bend, Kansas. License No. _____

Operation Completed: Hour 11:00PM Day 19 Month 11 Year 1968

The Above well was plugged as follows:

312'--8 5/8" Surface casing, cement circulated with 215 Sx.
Top of Dakota section @ 1425'.

Circulated hole with heavy mud. Pulled DP to 1650' and displaced 100 Sx. cement thru
DP from 1650' to 1325'. Pulled DP to 310' and displaced 20 Sx. cement thru DP from
310' to 250'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 11/26/68
INV. NO. 8874-W