

Y
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 27 1968
CONSERVATION DIVISION
Wichita, Kansas
08-27-1968

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-179-20126-00-00

Operator's Full Name Imperial Oil Company,

Complete Address: Box #784, Great Bend, Kansas.

Lease Name Hueftle Well No. 1

Location CNE-NW Sec. 28 Twp. 7 Rge. (E) (W) 30

County Sheridan Total Depth 4290

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 6:30 PM Day 24 Month 8 Year 1968

The Above well was plugged as follows:

280'--8 5/8" Surface pipe, cement circulated with 200 Sx.
Top of Dakota section @ 1425'.

Circulated hole with heavy mud. Pulled DP to 1650 and displaced 100 Sx. cement thru
DP from 1650' to 1325'. Pulled DP to 310' and displaced 20 Sx. cement thru DP from
310' to 250'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 8/27/68
INV. NO. 8360-11

Signed: W. D. Nichols
Well Plugging Supervisor