

Form CP-3
Rev. 6-26-62

KANSAS

M
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 19 1969
CONSERVATION DIVISION
Wichita, Kansas
03-19-1969

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-179-20177-00-00

Operator's Full Name Dreiling and Hiko Bell Mining & Oil Company,

Complete Address: R. R. #2, Victoria, Kansas.

Lease Name Gerdes Well No. 2

Location NE-SW-SW Sec. 13 Twp. 7 Rge. (E) (W) 30

County Sheridan Total Depth 4235'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: L. J. Dreiling and Sons, Incorporated,

Address: R. R. #2, Victoria, Kansas. License No.

Operation Completed: Hour 7:00 PM Day 17 Month 3 Year 1967

The Above well was plugged as follows:

274'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 1425.

Circulated hole with heavy mud. Pulled DP to 1650' and displaced 100 Sx. cement
thru DP from 1650' to 1325'. Pulled DP to 300' and displaced 20 Sx. cement thru DP
from 300' to 240'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement
to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 3/19/69
INV. NO. 9479-u

Signed: W. L. Nichols
Well Plugging Supervisor