



KANSAS

Form CP-3  
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 9 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
12-09-1968

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-179-20164-00-00

Operator's Full Name King Resources Company,

Complete Address: 100 Park Avenue Building, Suite #333, Oklahoma City, Oklahoma.

Lease Name Huber Well No. 1

Location CSW-SE Sec. 3 Twp. 7 Rge. (E) (W) 30

County Sheridan Total Depth 5000

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Gabbert-Jones, Incorporated,

Address: 830 Sutton Place, Wichita, Kansas. License No.     

Operation Completed: Hour 4:45PM Day 5 Month 12 Year 1968

The Above well was plugged as follows:

344'--8 5/8" Surface casing, cement circulated with 275 Sx.

Circulated hole with heavy mud. Pulled Dp to 1650' and displaced 100 Sx. cement thru

DP from 1650' to 1325'. Pulled DP to 360' and displaced 20 Sx. cement thru DP from

360' to 300'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to

bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Dickel  
Well Plugging Supervisor

INVOICED

DATE 12/9/68  
INV. NO. 8969-u