

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-179-20151-00-00

SEP 29 1975
09-26-1975
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Dreiling Oil, Inc.
Complete Address RT. 2 - Victoria Kansas, 67671
Lease Name Geerdes Well No. #1
Location SE-SE-SW Sec. 13 Twp. 7 Rge. 30 (E) (W)
County Sheridan Total Depth 4235'
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Dreiling Oil Inc.
Address RT-2 - Victoria Kansas, 67671 License No.
Operation Completed: Hour 10:30 PM Day 26 Month Sept Year 1975

The above well was plugged as follows:

K.B. 2911 - Dak Top. 1450' S.P. 302' of 8 5/8" cwc. 175 sx
4 1/2" set @ 4227. w/200 sx cem. Top of Cem. 3549'
Top Perf. 4068 Bottom Plug. w/25' of sand & 4 sx cem
Recovered 1245' of 4 1/2" casing. Pumped down 8 5/8" SP,
5 sx Halls & 80 sx cem. 50% Poz mix 60 Gel. & 27 sx Gel.
Released Plug. & 60 sx cem. 50% Poz mix 60 Gel.
Closing Pres. 100 Lbs Max Pres. 350 lbs.
Sum. Cementing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/30/75
INV. NO. 2004-W

Signed: Gilbert Patton
Well Plugging Supervisor