

KANSAS

AP
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-179-20346-00-00

RECEIVED
STATE CORPORATION COMMISSION
JAN 16 1973
01-16-1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name John O. Farmer, Incorporated.
Complete Address Box #352, Russell, Kansas.
Lease Name Gerdes Well No. 1
Location CSW-SE Sec. 13 Twp. 7 Rge. (E) (W) 30
County Sheridan Total Depth 4272'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Above
Address License No.
Operation Completed: Hour 2:00 AM Day 14 Month 1 Year 1973

The above well was plugged as follows:

268'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 1450'.

Circulated hole with heavy mud. Pulled DP to 1675' and displaced 110 Cu. Ft. cement
thru DP from 1675' to 1350'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *R. L. Nichole*
Well Plugging Supervisor

DATE 1/16/73
INV. NO. 6866-11