

KANSAS

Y
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 24 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-179-20283-00-00

05-24-1971

Operator's Full Name Nadel & Gussman,

Complete Address 514 Union Center Building, Wichita, Kansas.

Lease Name Teel Well No. 1

Location CSE-SE Sec. 18 Twp. 7 Rge. (E) (W) 30

County Sheridan Total Depth 4220'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Dreiling Oil, Incorporated,

Address R. R. #2, Victoria, Kansas. License No.

Operation Completed: Hour 11:45 PM Day 20 Month 5 Year 1971

The above well was plugged as follows:

325'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1450'.

Circulated hole with heavy mud. Pulled DP to 1675' and displaced 100 Sx. cement thru
DP from 1675' to 1350'. Pulled DP to 340' and displaced 25 Sx. cement thru DP from
340' to 265'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *W. L. Nichols*
Well Plugging Supervisor

DATE 5-24-71

INV. NO. 2750-10