

24

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 14 1969
CONSERVATION DIVISION
Wichita, Kansas
08-14-1969

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-179-20218-00-00

Operator's Full Name Chief Drilling Company, Incorporated,
Complete Address Box #797, Great Bend, Kansas,
Lease Name Yelek Well No. 1
Location CSW-NW Sec. 27 Twp. 7 Rge. (E) (W) 30
County Sheridan Total Depth 1300'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Above
Address License No.

Operation Completed: Hour 7:30 PM Day 8 Month 8 Year 1969

The above well was plugged as follows:

326'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 1175'.

Circulated hole with heavy mud. Pulled DP to 1700' and displaced 100 Sx. cement thru
DP from 1700' to 1375'. Pulled DP to 335' and displaced 20 Sx. cement thru DP from
335' to 275'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 8/14/69
INV. NO. 301-W