

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-065-03084-00-00
Well was completed on:

API NUMBER 1-22-59

LEASE NAME Fabricius Unit

WELL NUMBER 301

3300 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 26 TWP. 7S RGE. 23 (W)

COUNTY Graham

Date Well Completed 1-22-59

Plugging Commenced 4-18-88

Plugging Completed 4-18-88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR OXY USA Inc.

ADDRESS 3545 N.W. 58th Street, Oklahoma City, OK 73112

PHONE# (405) 949-4268 OPERATORS LICENSE NO. 5447

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on March 7, 1988 (date)

by District #4; Mr. Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? On: 1-22-59 If not, is well log attached? yes

Producing Formation LKC Depth to Top 3679 Bottom 3681 T.D. 3730
3685 3688
3690 3696

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|-----------|---------|------|------|--------|--------|------------|
| LKC | Oil | 3679 | 3681 | 8-5/8" | 223 | |
| | | 3685 | 3688 | 5-1/2" | 3730 | |
| | | 3690 | 3696 | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Perf. above the Anhy. at 1900 w/4 SPF & perf. below the Dakota at 940 w/3 SPF. Tied into the 5-1/2" csg. and filled to surface w/185 sx HDI cmt. & 500# cotton seed hulls. Tied onto the 8-5/8" csg. and pumped 2 sx HDI cmt. and 100# hulls & filled the annulus to surf.
State Witness: Mr. Carl Goodrow

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Service Co. License No. _____

Address Oberlin, KS 67749

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc.

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Bryan Humphries

(Employee of Operator) or (Operator) or

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Bryan Humphries 73112

(Address) 3545 N.W. 58th St., Okla. City, OK

SUBSCRIBED AND SWORN TO before me this 25th day of May, 19 88

Marsha G. Wilson
Notary Public

My Commission Expires: 4-1-92

RECEIVED
STATE CORPORATION COMMISSION
MAY 31 1988
CONSERVATION DIVISION
Wichita, Kansas
5/31/88