


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Graham County. Sec. 26 Twp. 7S Rge. 23W (E) (W)
Location as "NE/CNW/SW" or footage from lines C SE SE
Lease Owner Imperial Oil of Kansas, Inc.
Lease Name Fabricius "C" Well No. 3
Office Address 780 Fourth National Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed February 3, 1959
Application for plugging filed December 15, 1960
Application for plugging approved December 17, 1960
Plugging commenced January 6, 1961
Plugging completed January 8, 1961
Reason for abandonment of well or producing formation Commercial quantities of oil depleted.



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. A. D. Fabricius
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3775 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	223'	Not Pulled
				5-1/2"	3775'	" "

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Raised mast, checked hole. Sanded back to 3710' and run 3 sacks cement. Cleaned out cellar. Took tension on pipe. Worked tension to 28". Loaded hole with water. Checked hole and made shot at 3005'. Worked pipe free and pulled 65 jts. Pulled 28 jts. for total string of 93 jts. Mudded hole to 220' set 10' rock bridge. Mixed and run 25 sacks cement. With dump bailer mud to 35' set 5' rock bridge with 10 sacks cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
FEB 6 1961
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Southwest Casing Pulling Company
Address Great Bend, Kansas

2/6/61

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
R. L. Bacon (employee of owner) or (owner) or (operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL OIL OF KANSAS, INC.
(Signature) By: R. L. Bacon V-P
780 Fourth National Bldg., Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of February, 1961

My commission expires October 12, 1964
Cecilia C. Klug
Cecilia C. Klug Notary Public.



AL

15-065-02624-00-00

DRILLER'S LOG

Imperial Oil of Kansas, Inc.
780 Fourth National Bldg.
Wichita 2, Kansas

Fabricius "C" No. 3
C SE SE Sec. 26-7S-23W
Graham County, Kansas

Total Depth: 3775'

Elevation: 2309' RB
Production:

Commenced: 1-27-59 Completed: 2-3-59

Contractor: Imperial Oil of Kansas, Inc.
Wichita 2, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 223' with 165 sacks cement.
Set 5-1/2" Production Pipe at 3775' with 125 sacks cement.

Figures indicate bottom of formations:

Surface Sand & Clay	223'
Shells & Shale	1175'
Shale & Sand	1510'
Dakota Sand	1715'
Shells & Shale	1957'
Anhydrite	1991'
Shale & Shells	2490'
Shale & Lime	3340'
Lime	3435'
Shale & Lime	3525'
Lime	3775'
Total Depth	3775'

TOPS

Anhydrite	1957' (/ 352)
Heebner	3529' (-1220)
Toronto	3558' (-1249)
Lansing	3570' (-1261)
Rotary Total Depth	3775' (-1466)

We hereby certify this to be a correct and accurate log of the above described well as shown on the daily drilling reports.

IMPERIAL OIL OF KANSAS, INC.

By: Willard L. Hutchins
Secretary

Subscribed and sworn to before me this 27th day of February, 1959.

My Commission Expires:

July 7, 1962

RECEIVED
STATE CORPORATION COMMISSION

FEB 6 1961
CONSERVATION DIVISION
Wichita, Kansas

Mona L. Rater
Notary Public

2/6/61