

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-22,211-00-00

LEASE NAME Deines A-1

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 30 TWP. 7S RGE. 23W (E) or (W)

COUNTY Graham

Date Well Completed N/A

Plugging Commenced 9-3-85

Plugging Completed 9-3-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR D & D Production, Inc.

ADDRESS P. O. Box 321, 403 S. Main

PHONE#(316) 672-5002 OPERATORS LICENSE NO. 9514

Character of Well Dry Hole

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District 6, Hays

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation N/A Depth to Top Bottom T.D. 4,200 ft.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	248	8 5/8	248	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
180 sacks 60/40 poz mix with 6% gel, 1 sack flowseal, as follows: 20 sacks cement at 1969', 100 sacks cement, 1 sack flowseal at 1,175', 40 sacks at 300', 10 sacks at 40', 10 sacks at rathole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Western Kansas Drilling License No. unknown

Address 1111 East 30th, P. O. Box 126, Hays, Kansas 67601

STATE OF Kansas COUNTY OF Pratt, ss.


Darrel Anderson

(~~Employee of Operator~~) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Darrel Anderson

(Address) Box 321, Pratt, KS 67124

SUBSCRIBED AND SWORN TO before me this 13th day of December, 19 85



My Commission Expires:

Christine E. Davis
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

Form CP-4
Revised 08-84

12/16/85

DEC 16 1985

CONSERVATION DIVISION

D & D PRODUCTION, INC.
Producers of Oil and Gas
403 S. Main, P. O. Box 321
Pratt, KS 67124
(316) 672-5002

WELL LOG

Deines A-1
NE SE SE 30-7S-23W
Graham County, Kansas
Commenced 8-28-85
Completed 9-3-85
API #15-065-22,211-00-00
Operator: D & D Production, Inc.

From	Depth To	Formation	Remarks
0	1969	Anhydrite	Ran 250' new 8 5/8" surface casing. Set at 252' with 175 sxs 60/40 poz cement.
1969	2006	Base Anhydrite	
2006	3314	Topeka	Job by Allied. Plugged down at 1:45 a.m., August 27, 1985.
3314	3528	Heebner	
3528	3553	Toronto	
3553	3569	Lansing	
3569	3773	Base Kansas City	
3773	3956	Conglomerate	Well was plugged with 180 sxs 60/40 poz mix with 6% gel, 1 sack flowseal. Job by Allied. Plug down at 12:45 p.m., 9-3-85. State plugger was out of Hays, Kansas office.
3956	4200	TD	

STATE OF KANSAS, COUNTY OF PRAIRIE, SS:


I, the undersigned, being duly sworn on oath, state that the above Well Log is true and correct to the best of my knowledge and belief and according to the records of this office.

D & D PRODUCTION, INC.

Darrel Anderson
Darrel Anderson, President

Christine E. Davis
Notary Public

(SEAL)



STATE CORPORATION COMMISSION

DEC 16 1985
12/16/85
CORPORATION DIVISION
Wichita, Kansas