


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

15-065-00725-00-00
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Graham County. Sec. 34 Twp. 7S Rge. (E) 23 (W)
Location as "NE/CNW/SW" or footage from lines NE NE NW
Lease Owner Petroleum, Inc.
Lease Name DAWSON Well No. 1
Office Address 311 East Third, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 15 19 55
Application for plugging filed September 15 19 55
Application for plugging approved September 15 19 55
Plugging commenced September 15 19 55
Plugging completed September 15 19 55
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4068 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	202	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded up with heavy mud to 190' and set wooden
plug at 190'. Cemented and displaced 15 sacks cement through
drill pipe onto plug at 190'. Mudded up with heavy mud to 40'
and set second wooden plug at 40', placed 1/2 sack hulls on
top of plug at 40'. Filled hole to bottom of well cellar with
10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Company
Address R. R. #2 - Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Karl E. Becker (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Karl E. Becker
311 East Third, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of September, 19 55

Cherian Morris
Notary Public.

My commission expires August 8, 1959

PLUGGING
FILE SEC 34 T 7 R 23W
BOOK PAGE 2 LINE 14



CONSERVATION DIVISION
Wichita, Kansas

9/22/55

WELL LOG

15-065-00725-00-00

COMPANY **Petroleum, Inc.**

SEC. **34** T. **7S** R. **23W**

FARM **DANSON** NO. **1**


LOC. **N6 NE SW
330' FUL
2310' FUL**

TOTAL DEPTH **4068'**

COUNTY **Graham**

COMM. **September 5, 1955** COMP. **September 15, 1955**

CONTRACTOR **Garvey Drilling Company**



CASING **8-5/8" @ 202' w/150 #BX**

ELEVATION **2362' NG
2364' NG**

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

145	Clay & Sand
190	Shale
202	Sand, Rock & Iron
205	Sand Rock & Shale
2015	Sand, Shale & Shells
2030	Shale
2100	Anhydrite
2350	Shale & Shells
2770	Lime & Shale
2930	Shale & Sand
2977	Shale
3645	Lime & Shale
3825	Lime
4038	Shale & Lime
4066	Lime & Chert
4068	Lime

Sample Logs

Rockner:	3595	(-1231)
Toronto:	3618	(-1254)
Leasing:	3635	(-1271)
Conglomerate:	3992	(-1628)
Congl. Chert:	4008	(-1644)
Arbuckle:	4318	(-1954)

R.T.D. 4068'

State of KANSAS

County of SENECA

PLUGGING
FILE SEC 34 T. 7 R. 23W
BOOK PAGE 9 LINE 14

9/22/55

I, Karl E. Becker

of Petroleum, Inc.

upon oath state that the above and foregoing is a true and correct copy of the log of the DANSON #1 well

RECEIVED
STATE CORPORATION COMMISSION

CORPORATION DIVISION
KANSAS

Subscribed and sworn to before me this 20th day of September 19 55

My Commission Expires: August 8, 1959

Karl E. Becker

Floris Morrison
NOTARY PUBLIC