

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-20,635 - 00-02

LEASE NAME Dawson

WELL NUMBER #1

3300 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 34 TWP. 7s RGE. 23 (E) or (W)

COUNTY Graham

Date Well Completed 9-23-55

Plugging Commenced 6-28-91

Plugging Completed 6-28-91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Rider Oil & Gas Exploration, Inc.

ADDRESS 2805 Bentbay Circle - Wichita, KS 67204

PHONE# (316) 838-9069 OPERATORS LICENSE NO. 7802

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6-27-91 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Kansas City Depth to Top 3738 Bottom 3772 T.D. 3840'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
KC		195	0	8 5/8		200 sk
		3839	0	5 1/2		200 sk

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Down 5 1/2" casing at 500 # max pressure, mixed 7 sks hulls w/275 sks cement and shut in at 200#. down annulus 8 5/8" casing at 400# max pressure, mixed 3 sks hulls with 75 sks cement and shut in at 200#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing, Inc. License No. _____

Address Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Rider Oil & Gas Exploration, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Don V. Rider (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Don V. Rider


(Address) 2805 Bentbay Circle, Wichita, KS 67204

RECEIVED
STATE CORPORATION COMMISSION

SUBSCRIBED AND SWORN TO before me this 15th day of July, 19 91

7/17/91
JUL 17 1991

My Commission Expires 1992



Notary Public

CONSERVATION DIVISION
Wichita, Kansas