

STATE OF KANSAS
STATE CORPORATION COMMISSION

15-065-026² - 00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Graham

County. Sec. 35 Twp. 7S Rge. 23W (E) (W)

Location as "NE/CNW/SW" or footage from lines C NW NE

Lease Owner Imperial Oil of Kansas, Inc.

Lease Name Wanker Well No. 3

Office Address 780 Fourth National Bldg., Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed May 8 1959

Application for plugging filed May 8 1959

Application for plugging approved May 8 1959

Plugging commenced May 8 1959

Plugging completed May 8 1959

Reason for abandonment of well or producing formation No commercial quantities of oil found.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. A. D. Fabricius

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3810 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8" | 216' | 216' |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

No. 1 Plug set at 550' with 20 sacks cement; No. 2 Plug set at 210' with 20 sacks of cement; No. 3 Plug at 40' with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
JUN 24 1959
CONSERVATION DIVISION
WICHITA, KANSAS
6/24/59

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Imperial Oil of Kansas, Inc.
Address 780 Fourth National Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Raymond L. Bacon (employee of owner or contractor) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL OIL OF KANSAS, INC.

(Signature) By: Raymond L. Bacon
780 Fourth National Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of June, 19 59

My commission expires July 7, 1962

Mona L. Latier
Mona L. Latier Notary Public.

PLUGGING
FILE SEC 35 T. 7 R. 23W
BOOK PAGE 46 LINE 19

15-065-02626-00-00

DRILLER'S LOG

Imperial Oil of Kansas, Inc.
780 Fourth National Bldg.
Wichita 2, Kansas

Wanker No. 3
C NW NE Sec. 35-7S-23W
Graham County, Kansas

Total Depth: 3810'

Elevation: 2356' R.B.
Production: D & A

Commenced: 4-30-59 Completed: 5-8-59

Contractor: Imperial Oil of Kansas, Inc.
Wichita 2, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 216' with 165 sacks cement.

Figures indicate bottom of formations:

| | | <u>TOPS</u> | |
|-----------------------------|-------|--------------------|-----------------|
| Clay, Shale & Sand | 216' | Anhydrite | 2009' (/ 349) |
| Shale, Shells & Sand | 1360' | Heebner | 3576' (-1218) |
| Dakota Sand, Shale & Shells | 1760' | Toronto | 3599' (-1241) |
| Shale & Red Bed | 2009' | Lansing | 3616' (-1260) |
| Anhydrite | 2043' | Rotary Total Depth | 3810' (-1454) |
| Shale & Shells | 2495' | | |
| Shale & Lime | 3665' | | |
| Lime | 3810' | | |
| Total Depth | 3810' | | |

We hereby certify this to be a correct and accurate log of the above described well as shown on the daily drilling reports.

IMPERIAL OIL OF KANSAS, INC.

By: *A. Bacon*
Vice-President

Subscribed and sworn to before me this 18th day of May, 1959.

My Commission Expires:

July 7, 1962

RECEIVED
STATE CORPORATION COMMISSION

JUN 24 1959

CONSERVATION DIVISION
Wichita, Kansas

6/24/59

Mona L. Latier
Mona L. Latier - Notary Public

PLUGGING
FILE SEC 35 T 7 R 23W
BOOK PAGE 46 LINE 19