

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

RECEIVED FEB 27 2006 KCC WICHITA Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Beren Corp. Address: PO Box 723 Hays, KS 67601 Phone: (785) 628-6101 Operator License #: 5364 Type of Well: Oil Docket #: The plugging proposal was approved on: 2-15-06 by: Herb Dienes (KCC District Agent's Name) Is ACO-1 filed? [X] Yes [ ] No If not, is well log attached? [ ] Yes [ ] No Producing Formation(s): List All (If needed attach another sheet) Toronto Depth to Top: 3789 Bottom: 97 T.D. KC Depth to Top: 3806 Bottom: 401' T.D.

API Number: 15-065-20463-00-00 Lease Name: Brungardt B Well Number: B-2 Spot Location (QQQQ): E-S - 2-S - 2-NW - KCC 2970 Feet from [ ] North / [X] South Section Line PK1 3960 Feet from [X] East / [ ] West Section Line Per cpj Sec. 22 Twp. 10 S. R. 25 [ ] East [X] West County: Graham Date Well Completed: 7-22-71 Plugging Commenced: 2-15-06 Plugging Completed: 2-15-06

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Oil, Gas or Water Records (Formation, Content), Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Rows include Toronto and KC 3806-4011.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Tag up on Lockset at 3495' no fill on lockset. Release lockset and TOH. TIH with 2-3/8 tbg. Tag at 3590' acts like iron, rig up allied spot 50 sks 60/40 10% gell with hulls, pull tbg to 3000' spot 50 sks with hulls pull tbg to 2400' spot 50 sks with hulls, pull tbg to 1800' spot 50 sks with hulls, pull tbg to 1200' spot 50 sks with hulls, cement circulated. TOH with tbg. rig down dug cellar out tie onto 8-5/8 pump 100sks with hulls psi to 300# and holding tie onto 5-1/2" csg and pump 30 sks with hulls psi to 400# and holding. Rig down.

Name of Plugging Contractor: Beren Corp License #: 5364 Address: PO Box 723 Hays, KS 67601

Name of Party Responsible for Plugging Fees: Beren Corp.

State of Kansas County, Graham, ss.

Mark Leiker (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Mark Leiker

(Address) PO Box 723 Hays, KS 67601

SUBSCRIBED and SWORN TO before me this 24 day of February, 2006 SHANNA MILLER NOTARY PUBLIC My Commission Expires: 9/19/09

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202