

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Duncan Oil Properties, Inc.  
Address: 100 Park Avenue, Suite 1200  
Phone: (405) 272-1800 Operator License #: 33430  
Type of Well: D & A Docket #: \_\_\_\_\_  
*(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other)* *(If SWD or ENHR)*  
The plugging proposal was approved on: 09-22-2005 (Date)  
by: Montgomery, Barba (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-119-21164-00-00  
Lease Name: Clayton  
Well Number: 1-34  
Spot Location (QQQQ): \_\_\_\_\_ - NW - SW - SW  
1120 Feet from  North /  South Section Line  
330 Feet from  East /  West Section Line  
Sec. 34S Twp. 33S S. R. 29  East  West  
County: Meade  
Date Well Completed: 09-04-2005  
Plugging Commenced: 09-02-2005  
Plugging Completed: 09-03-2005

*KCC 3-20-06  
per operator  
per Walta*

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		Surface	1234'	8 5/8	1234'	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Cement Plugs set thru DP as follows: Pump 8 1/2 bbls wtr ahead; @ 1450' Pump 30 sx cement. Disp 3 bbls fresh wtr. Follow w/ 15 1/2 bbls mud.  
Pull pipe to 1280'. Pump 8 1/2 bbls fresh wtr ahead, Pump 50 sx 6040 cement. Disp w/ 3 bbls fresh wtr. Finish Disp w/ 11 1/2 bbls mud. Pull up to 600'. Pump 20 bbls fresh wtr ahead. Pump 50 sx 60:40:6; disp 4 1/2 bbl fresh wtr. Come up to 40'. Pump 10 sx 60:40:6 to top off center.  
Pump 15 sx 60:40:6 in rat hole. Cement Plugs @ 1450'; 1280'; 600'; 40' to surface.

Name of Plugging Contractor: Big A Drilling License #: 31572  
Address: 100 South Main, Suite 508, Wichita, KS 67202

**RECEIVED**  
KANSAS CORPORATION COMMISSION  
MAR 10 2006

Name of Party Responsible for Plugging Fees: Duncan Oil Properties, Inc.  
State of Oklahoma County, Oklahoma, ss.

CONSERVATION DIVISION  
WICHITA, KS

Walta Rollin, Production Technician (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Walta Rollin  
(Address) 100 Park Ave, Ste 1200, Oklahoma City, OK 73102

SUBSCRIBED and SWORN TO before me this 9th day of March, 20 06  
Debra S Pope My Commission Expires: \_\_\_\_\_  
Notary Public

NOTARY SEAL  
DEBRA S. POPE  
Notary Public  
State of Oklahoma  
Commission # 01005201 Expires 4/28/09

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*PAM*