

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
Amended WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Chesapeake Operating, Inc.
Address: P.O. Box 18496, Oklahoma City, OK 73154-0496
Phone: (405) 848-8000 Operator License #: 32334

Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: faxed 2/7/2006 (Date)

by: David Williams (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)
Winfield Depth to Top: 2340 Bottom: 2348 T.D. 2410

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-075-20322-00-00
Lease Name: Johnston Johnson *KCC 3-28-06 Pkt Per CP2/3.*

Well Number: 1 A

Spot Location (QQQQ): _____ - _____ - _____ - SE
1320 Feet from North / South Section Line

1320 Feet from East / West Section Line

Sec. 20 Twp. 24 S. R. 40 East West

County: Hamilton

Date Well Completed: 2/17/1977

Plugging Commenced: 2/9/2006

Plugging Completed: 2/9/2006

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		0	552'	8-5/8"		
		0	2409'	5-1/2"		

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Pump 300# hulls in gel plug down 4-1/2" casing, followed by 25 sx cement, pump 115 sx 60/40 P0Z with 6% gel, fill 4-1/2" casing to surface, press to 500 PSIG tie onto 8-5/8" casing, pump 2 bbls csg loaded, no injection at 300 PSIG. Weld on cap. restore location.

Name of Plugging Contractor: Allied Cementing Co., Inc. License #: None required 99996

Address: P.O. Box 31, Russell, KS 67665

Name of Party Responsible for Plugging Fees: Chesapeake Operating, Inc.

State of Oklahoma County, Oklahoma, ss.

Jim Reisch, Asset Manager (Employee of Operator) or (Operator) on above-described well, being first duly


sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) *Jim Reisch*

(Address) P.O. Box 18496, Oklahoma City, OK 73154-0496

SUBSCRIBED and SWORN TO before me this 22nd day of March, 20 06

Renee Riebe My Commission Expires: 4-5-08
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202