

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: MIDCO Exploration, Inc.
Address: 414 Plaza Drive, Suite 204
Phone: (630) 655-2198 Operator License #: 5254
Type of Well: D&A Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 2/14/2006 (Date)
by: Dodge City office (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 025-21339-0000
Lease Name: Bisel
Well Number: 4-3
Spot Location (QQQQ): NE - NE - SW - NE
1485 Feet from North / South Section Line
1485 Feet from East / West Section Line
Sec. 3 Twp. 34 S. R. 23 East West
County: Clark
Date Well Completed: _____
Plugging Commenced: 2/14/2006
Plugging Completed: 2/14/2006

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		0	103	20"	103	0
		0	777	8 5/8"	777	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

First plug 930' ; load hole; pump 50 sx 60:40:6 ; displace with mud/fresh water;
Second plug 250' ; load hole; pump 40 sx 60:40:6 ; displace with fresh water;
Third plug 60' ; load hole; pump 25 sx 60:40:6 ; circulate cement to surface.
Plug rat and mouse holes with 25 sx 60:40:6. - (60% common A; 40% pozmix; 6% gel)

Name of Plugging Contractor: Murfin Drilling Co., Inc. License #: 30606
Address: 250 N Water #300 Wichita, KS 67202
Name of Party Responsible for Plugging Fees: MIDCO Exploration, Inc.

State of Illinois County, DuPage, ss.
Earl J. Joyce, Jr.

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) _____
(Address) 414 Plaza Drive, Suite 204 Westmont, IL 60559

SUBSCRIBED and SWORN TO before me this 21st day of March, 20 06
OFFICIAL SEAL
Nancy L. Macynas My Commission Expires: Nancy L. Macynas
Notary Public, State of Illinois
Commission Exp. 06/24/2006

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
MAR 27 2006
KCC WICHITA

Jan