

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: American Warrior INC
Address: P.O.Box 399, garden City, KS 67846
Phone: (620) 275-2963 Operator License #: 4058
Type of Well: OIL Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 1-19-06 (Date)
by: Herb Deines (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Arbuckle Depth to Top: 3301 Bottom: 3303.5 T.D. 3303.5
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-009-14,328-00-00
Lease Name: pANNING
Well Number: 7
Spot Location (QQQQ): C - SW - NW - SE
1650' Feet from North / South Section Line
2310' Feet from East / West Section Line
Sec. 3 Twp. 20S S. R. 11 East West
County: Barton
Date Well Completed: 1953
Plugging Commenced: 1-23-06
Plugging Completed: 1-24-06

KCC
3-27-06
PKT
per oper.
Nancy

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	141	surface	8-5/8"	141'	none
	Production	3301	surface	7"	3301'	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perf.4 holes @ 1325'&500', ran tbg to 2015', pump 125 sks, &300#s hulls, pull TBG, to 1325' pump 100 sks cem & 300#s hulls, pull TBG to 500" circulate cement to surface w/ 75 sks cem & 400#s hulls pull TBG, hook-up to 7" pump 20 sks cem, press to 500#s SI, (cement 60/40 poz 10% gel,) Annulas already cemented to surface.

Name of Plugging Contractor: Allied Cementing Co. License #: NA 99996
Address: P.O.Box 31, Russell Ks 67665
Name of Party Responsible for Plugging Fees: American Warrior INC
State of Kansas County, Finney, ss.
Kevin Wiles SR/Prod. Supt. (Employee of Operator) or (Operator) on above-described well, being first duly

RECEIVED
FEB 21 2006
KCC WICHITA

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Handwritten Signature]
(Address) Sama As Above

ERICA KUHLMIEER
Notary Public - State of Kansas
My Appt. Expires 09-22-09

SWORN TO before me this 15th day of February, 20 06
Erica Kuhlmeier My Commission Expires: 09-22-09
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Pam