

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

Docket #E13043  
API NUMBER 15-163-20100-0000

LEASE NAME Bergier

WELL NUMBER #1 W

         Ft. from S Section Line

         Ft. from E Section Line

SEC. 33 TWP. 8 RGE. 16 (E) or (W)

COUNTY Rooks

Date Well Completed         

Plugging Commenced 6/12/90

Plugging Completed 6/12/90

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Murfin Drilling Company

ADDRESS Box 130 Hill City, KS 67642

PHONE#(913) 674-2101 OPERATORS LICENSE NO. 6033

Character of Well Injection

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on          (date)

by District #6, Hays Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed?          If not, is well log attached? Yes

Producing Formation LKC Depth to Top 3116 Bottom 3258 <sup>PBTD</sup> ~~KCC~~ 3281  
T.D. 3365

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	190'	0
				4 1/2	3364'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Perforated Anhydrite @ 1258' & Dakota @ 825'. Pumped down 4 1/2" Casing w/250 sx 65/35 Poz w/10% Gel & 400# hulls. Max PSI 1000#, ISIP 250 #. Pumped down 8 5/8 w/50 sx 65/35 Poz w/10% Gel & 100# hulls. Max PSI 500#, ISIP 400#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Murfin Drilling Company License No. 6033

Address 250 N. Water, Suite 300 Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company

STATE OF Kansas COUNTY OF Graham, ss.

John Gerstner, Production Foreman

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) John Gerstner

(Address) Box 130, Hill City, KS 67642

AND SWORN TO before me this 13th day of June, 19 90

Donna Gerstner  
Notary Public

My Commission Expires: 6/24/93



JUN 15 1990  
CONSERVATION DIVISION  
Wichita, Kansas  
6/15/90