

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION**
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
**This Form must be Typed
Form must be Signed
All blanks must be Filled**

API # 15 - 163-01618-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date _____.

Well Operator: Gore Oil Company KCC License #: 5552
(Owner / Company Name) (Operator's)

Address: P.O. Box 2757 City: Wichita

State: KS Zip Code: 67201-2757 Contact Phone: (316) 263 - 3535

Lease: Rostocil Well #: C-4 Sec. 10 Twp. 9 S. R. 19 East West

SE - NW - NW - Spot Location / QQQQ County: Rooks

4290 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

4290 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" Set at: 310' Cemented with: 175 Sacks

Production Casing Size: 5 1/2" Set at: 3440' Cemented with: 150 Sacks

List (ALL) Perforations and Bridgeplug Sets: AD-1 packer @ 3224'

Elevation: 2025' (G.L. / K.B.) T.D.: 3443' PBTD: _____ Anhydrite Depth: 1445'
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): As per KCC District Agent's instructions.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

**RECEIVED
MAR 27 2006
KCC WICHITA**

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Lenny Dinkel

Phone: (308) 345 - 1597

Address: P.O. Box 878 City / State: McCook, NE 69001

Plugging Contractor: Swift Services, Inc. KCC License #: 32382
(Company Name) (Contractor's)

Address: P.O. Box 466, Ness City, KS 67560-0466 Phone: (785) 798 - 2300

Proposed Date and Hour of Plugging (if known?): 3/8/06 - 8:00 AM

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 3-23-06 Authorized Operator / Agent: Lenny M Jaech
(Signature)

Mail to: KCC - Conservation Division, 150 S. Market - Room 2078, Wichita, Kansas 67202

*** well already plugged - KCC**

WELL LOG

SOHIO PETROLEUM COMPANY

RECEIVED
MAR 27 2006
KCC WICHITA
SE NW NW Sec. 10,
T-9, R-19W,
Rooks County, Kansas

Lease: Rostocil " C " No. 4

Elevation: 2023 derrick floor.

Note: All measurements from rotary bushings.

0	5 Cellar
5	150 Post rock & clay
150	275 Blue shale
275	310 Shale & shells
310	650 Shale & shells
650	915 Shale & shells
915	1140 Sand
1140	1250 Shale & shells
1250	1335 Shale & shells
1335	1425 Sand & shale
1425	1435 Anhydrite
1435	1468 Anhydrite
1468	1655 Shale & shells
1655	1800 Shale & shells
1800	1915 Lime & shale
1915	2050 Lime & shale
2050	2125 Lime & shale
2125	2275 Lime & shale
2275	2360 Lime & shale
2360	2390 Shale & Lime
2390	2485 Shale & Lime
2485	2620 Shale & Lime
2620	2760 Shale & Lime
2760	2860 Shale & Lime
2860	2950 Shale & Lime
2950	2960 Lime & shale
2960	3025 Lime & shale
3025	3105 Lime & shale
3105	3165 Lime & shale
3165	3215 Lime
3215	3225 Lime
3225	3290 Lime
3290	3340 Lime
3340	3380 Lime
3380	3400 Lime
3400	3440 Lime
3441 1/2	T.D. (rotary bushing meas.)

COMMENCED: 8- 8-50
COMPLETED: 8*19-50

CASING RECORD:

8 5/8" Surface casing set at 310' w/175 sacks cement by Halliburton.

5-1/2" production casing set at 3440 1/2', one foot off bottom w/150 sacks cement by Halliburton.

D.S.T. by Johnson Testing Co.

3195' to 3225' tool open 1hr. Weak steady blow through out. Recovered 120' heavily oil cut mud. B.H.P. 10 min. 1070#. F.P.-0.

3355' to 3380' tool open 1 hr. Recovered 35' heavily oil cut mud. B.H.P. 15 min. 320#. F.P.-0.

Ran Schlumberger Log and Micro Log, at total depth.

TOPS

Anhydrite	1445	Lansing	3193
Topeka	2950	Arbuckle	3439
Heebner	3154	T.D.	3441 1/2

I hereby affirm that the above and foregoing is a true and correct copy of the log of the Rostocil " C " No.4, located SE NW NW Sec. 10, T-9, R-19W, Rooks County, Kansas.

Strain Drilling Company.

By T.C. Strain
T.C. Strain.