

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-03177-00-00
Spot: NWSESW Sec/Twnshp/Rge: 12-15S-18W
990 feet from S Section Line, 3630 feet from E Section Line
Lease Name: BROCK Well #: 5
County: ELLIS Total Vertical Depth: 3654 feet

Operator License No.: 9090
Op Name: CHARTER ENERGY, INC.
Address: PO BOX 252
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	3646	0	200 SX CMT
SURF	10.75	354	0	200 SX CMT

\$118.76

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/30/2006 8:30 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: STEVE BAIZE Company: CHARTER ENERGY, INC. Phone: (785) 798-2300

Proposed Plugging Method: Ordered 150 sxs Swift Multi-Density Cement and 600# hulls.
Junk in the hole - hit iron at 1140'.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/30/2006 10:30 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Swift rigged to 10 3/4" and pumped 1/2 bbl SMD with instant pressure.
Max. P.S.I. 500#. S.I.P. 300#.
RIH with tubing to 1140' - rigged to tubing and pumped 50 sxs SMD neat, followed with 90 sxs and 600# hulls mixed in to circulate cement into pit.
Pulled tubing - rigged to 7" casing with a swedge and pumped 10 sxs.
Max. P.S.I. 800#. S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
3599	3604		
3322	3479		

INVOICED
4-5-06
2006061420

Remarks: SWIFT SERVICES, INC. - TICKET #9722.

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

RECEIVED

APR 05 2006

KCC WICHITA

Form CP-2/3

MAR 31 2006

PAT

12-15-18W
 NW SE SW
 #5 BROCK
 SAUVAGE & DUNN
 ELLIS
 2016RB
 3-23-56
 200 BOPD/ARB

DON PRATT

#5 BROCK

12-15-18W
NW SE SW

Contr. SAUVAGE & DUNN ELLIS County
 E 2016RB Comm. 3-23-56 IP 200 BOPD/ARB

Tops	Depth	Datum
		*
HEEB	3250	-1234
LANS	3300	-1284
ARB	3600	-1584
TD	3654	-1638

Casing
 10" 370
 5" 3654

*10 3/4 - 354 w/2005x5
 well had 7" to 3646 w/2005x5
 A.S. 3-30-06*

PERF 3600-05: 8 BOPH

LEIKER EAST POOL

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS