

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-03178-00-00
Spot: SENWSW Sec/Twnshp/Rge: 12-15S-18W
1650 feet from S Section Line, 4290 feet from E Section Line
Lease Name: BROCK Well #: 6
County: ELLIS Total Vertical Depth: 3648 feet

Operator License No.: 9090
Op Name: CHARTER ENERGY, INC.
Address: PO BOX 252
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	3643	0	200 SX CMT
SURF	10.75	350	0	200 SX CMT

118.56

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/30/2006 11:00 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: STEVE BAIZE Company: CHARTER ENERGY, INC. Phone: (785) 798-2300

Proposed Plugging Method: Ordered 320 sxs Swift Multi-Density Cement and 600# hulls.
Well has casing leaks. Squeeze at 560' - 675'.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/30/2006 3:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Swift rigged onto 10 3/4" casing and pumped 1/2 bbl SMD with instant pressure.
Max. P.S.I. 1000#. Blew small hole on weld on nipple to well head. No S.I.P.
RIH with tubing to 2000'. Swift rigged to tubing and pumped 110 sxs SMD with 300# hulls mixed in.
Pulled tubing to 1600'. Swift pumped 150 sxs SMD with 300# hulls mixed in - well pressured to Max P.S.I. 1000#.
Pulled tubing to 700'. Swift rigged to tubing and pumped 60 sxs SMD to circulate cement to surface.
Pulled tubing - tied onto 7" casing and pumped one barrel.
Max. P.S.I. 200#. S.I.P. 50#.

Perfs:

Top	Bot	Thru	Comments
3585	3590		
3331	3408		

Remarks: SWIFT SERVICE, INC. - TICKET #9723

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

MAR 31 2006

RECEIVED
APR 05 2006
KCC WICHITA

Form CP-2/3

INVOICED

4-5-06

2006061420

PAT

WADICEN

DON PRATT

#6 BROCK

12-15-18W
SE NW SW

Contr. _____ ELLIS _____ County

E 2018 Comm. _____ Comp. 4-20-56 IP 134 BOPD/ARB

Tops	Depth	Datum
		7
HEEB	3250	-1232
KC	3305	-1287
CONG	3560	-1542
ARB	3582	-1564
TD	3648	-1630

Casing
 10" 350/w 200 x 5
~~5" 3648~~
 7"-3643 w/ 200 x 5
 PERF 3580-85: ACID 500: 10
 BOPH: SQZ: REPERF 3585-90
 ACID 500

LEIKER EAST

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS