

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-21266-00-00
Spot: W2NWSESW Sec/Twnshp/Rge: 29-9S-22W
990 feet from S Section Line, 3940 feet from E Section Line
Lease Name: BRASSFIELD Well #: 2
County: GRAHAM Total Vertical Depth: 3985 feet

Operator License No.: 5430
Op Name: ENERGY THREE, INC.
Address: 1437 OLD SQUARE RD #201A
JACKSON, MS 39211

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3895	0	w/125 sxs cmt
SURF	8.625	265	0	w/175 sxs cmt

\$1 129.51

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/30/2006 9:30 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: TIM SCHECK Company: ENERGY THREE, INC. Phone: (785) 637-5321

Proposed Plugging Method: Ordered out 275 sxs 60/40 pozmix - 10% gel - 500# hulls.
TOF at 3689' - packer and 6 joints tubing.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/30/2006 2:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perfs:

Perforated casing at 1175' and 1930'.
TIH with tubing to 3590' - mixed and circulated cement with 210 sxs.
POOH. Hooked up to the annulus and pumped 50 sxs cement. S.I.P. 200#.
Topped off 4 1/2" with 15 sxs.

INVOICED

DATE 4-5-06
W.B. NO. 2006061421

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

100-

Signed _____

Jay Pfeifer
RECEIVED

(TECHNICIAN)

APR 05 2006

KCC WICHITA

Form CP-2/3

MAR 31 2006

pet

INDEXED

ENERGY THREE INC
P.O. BOX 1505

#2 BRASSFIELD 310'W, NW SE SW 29-9-22W

GREAT BEND, KS 67530
CONTR BIG SPRINGS DRILG.

CTY GRAHAM

GEOL JERRY GREEN

FIELD RED LINE NW

E 2385 KB CM 8/25/80 CARD ISSUED

10/23/80 IP P 100 BOPD NW
LKC 3823-3827

+	+
+	+
+	+
+	+

API 15-065-21,266

SMP	TOPS	DEPTH	DATUM.
ANH		1897	+ 488
TOP		NOT CALLED	
HEEB		3597	-1212
TOR		3621	-1236
LKC		3635	-1250
MARM		3937	-1552
RTD		3985	-1600
NO LOG			

8 5/8" 265/175sx; 4 1/2" 3895/125sx

DST (1) 3628-3710/60-45-30-45, REC 620'
SOCMW, SIP 739-739#, FP 87-251/
295-338#

DST (2) 3798-3818/60-45-30-45, REC 50'
MCO, 240'CGO, SIP 295-295#, FP
22-55/87-98#

DST (3) 3816-3840/60-45-30-45, REC 30'M
SIP 625-545#, FP 57-68/80-80#

MICT - CO, PF 3823-3827, AC 1000 GALS,
SWB 20 BOPH, POP, P 100 BOPD NW

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS