

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-20045-00-00
Spot: SENWSE Sec/Twnshp/Rge: 8-10S-17W
1650 feet from S Section Line, 1650 feet from E Section Line
Lease Name: WHITE B Well #: 1
County: ROOKS Total Vertical Depth: 3570 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: 202 SOUTH ST. FRANCIS PO BOX 2757
WICHITA, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3568	0	w/275 sxs cmt
SURF	8.625	178	0	w/135 sxs cmt

\$1 116.03

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/03/2006 1:30 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: LENNY DINKEL Company: GORE OIL COMPANY Phone: (785) 259-1928

Proposed Plugging Method: Ordered out 150 sxs Swift Multi-Density Cement.
Pulled rods and pump out - tubing stuck at 2265'.
Unable to wash over past 2304' - circulated drilling mud and formation out.
Decided to P&A.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/03/2006 4:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 2304'. Swift Services pumped 80 sxs SMD with 300# hulls - circulated cement. PTOH. Squeezed with 10 sxs. Max P.S.I. 500#. S.I.P. 500#. Hooked up to backside and pumped 60 sxs. Max. P.S.I. 300#. S.I.P. 100#.

Perfs:

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

INVOICED
4-5-06
2006061423

District: 04

TD

Signed

Richard Williams

(TECHNICIAN)

RECEIVED

APR 05 2006

KCC WICHITA


Form CP-2/3

APR 04 2006

NOT

2095 KB
 8/1/67
 9/14/67

DAVIS BROS. #B-1 WHITE 8-10-17W
 SE NW SE
 Contr. LEBEN DRLG Cty. ROOKS
 Geol. Pool PLAINVILLE EXT
 E. 2095 KB Cm. 8/1/67 Cp. 9/14/67 IP P 75 BOPD + 25
 BWPD/LANS 3424-
 API 15-163-20,045 30, 3435-38, 3553-59,



SMP Tops	Depth	Datum
ANHY	1368	+ 727
B/ANHY	1405	+ 690
TOP	3027	- 932
HEFB	3246	-1151
TOR	3266	-1171
LKC	3289	-1194
BKC	3522	-1427
CONG	3546	-1451
RID	3570	-1475

Csg. 3492-95, 3512-18.
 8" 178/135 SX
 4" 3568/275 SX
 DST 3410-3525/2', 30' VHOCM, 110'
 OCM, BHP 929-724#/20", FP
 85-103#
 PF 12/3492-95 24/3512-18, SWB 15
 GF 1' (50% OIL) A 500 + 3500 ACID
 SWB 63 BF (80% OIL) SWB 5 BOPH/4
 HRS, PF 3453-59, PF 3470-78, A
 4250, REC 60 BF, 50% OIL, 25 BO/
 HRS, PF 3424-30, 3435-38, SWB 5.8
 BO, NW/1 HRS, A 2500, CO PLUGS,
 POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS