

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-137-20452-00-00
Spot: N2W2SWSW Sec/Twnshp/Rge: 33-3S-23W
905 feet from S Section Line, 370 feet from W Section Line
Lease Name: HARTING Well #: 1
County: NORTON Total Vertical Depth: 3930 feet

Operator License No.: 33629
Op Name: GREAT PLAINS ENERGY, INC.
Address: PO BOX 292
WAHOO, NE 68066

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	393		

\$127.73

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/01/2006 12:00 AM
Plug Co. License No.: 33607 Plug Co. Name: KALER OIL COMPANY
Proposal Rcvd. from: DAN BLACKENNA Company: GREAT PLAINS ENERGY, INC. Phone: (402) 443-6125

Proposed Plugging Method: Ordered 225 sxs 60/40 pomix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: JAY PFEIFER Witness Type: NONE
Date/Time Plugging Completed: 04/01/2006 3:00 AM KCC Agent: JAY PFEIFER

Actual Plugging Report:

1st. Plug at 3800' w/25 sxs.
2nd. Plug at 2110' w/25 sxs.
3rd. Plug at 1325' w/100 sxs.
4th. Plug at 425' w/40 sxs.
5th. Plug at 40' w/10 sxs. 8 5/8" wiper plug.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

INVOICED
4-5-06
2006061424

District: 04

Signed _____

Jay Pfeifer
(TECHNICIAN)

RECEIVED
APR 05 2006

Form CP-2/3

APR 03 2006

KCC WICHITA

PET