

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-207-26950-00-00  
Spot: W2E2SESW Sec/Twnshp/Rge: 26-23S-13E  
660 feet from S Section Line, 3165 feet from E Section Line  
Lease Name: BERRY Well #: 1-A-05  
County: WOODSON Total Vertical Depth: 1855 feet

Operator License No.: 31772  
Op Name: BLACK STAR 231 CORP.  
Address: 5705 NW 90TH TERRACE  
KANSAS CITY, MO 64154

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	40	0	16 SX CMT

\$60.29

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/14/2005 11:00 AM  
Plug Co. License No.: 31440 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC  
Proposal Rcvd. from: JIM PRYOR Company: \_\_\_\_\_ Phone: (816) 560-7300

Proposed Plugging Method: SPOT CEMENT PLUGS IN HEAVY DRILLING MUD THROUGH DRILL PIPE. 15 SX @ 1810', 15 SX @ 1580', 15 SX @ 920', 95 SX @ 95' TO SURFACE, 10 SX IN RAHTHOLE.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: NONE  
Date/Time Plugging Completed: 11/14/2005 1:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

Perfs:

DRILL PIPE WAS RAN TO T.D.. 15 SACKS OF CEMENT WERE PUMPED THROUGH THE DRILL PIPE TO T.D.. THE PIPE WAS PULLED TO 1500' AND 15 SACKS OF CEMENT WERE PUMPED TO THAT DEPTH. THE PIPE WAS PULLED TO 900' AND 15 SACKS OF CEMENT WERE SPOTTED AT 900'. THE PIPE WAS PULLED TO 250'. CEMENT WAS PUMPED INTO THE DRILL PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE DRILL PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

RECEIVED  
KCC DISTRICT #3  
MAR 29 2006 CPT  
CHANUTE, KS

Remarks:

Plugged through: DP

District: 03

Signed Clayton P. Titel  
(TECHNICIAN)

INVOICED  
APR 13 2006  
200606141  
KCC WICHITA

PBT