

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-011-23161-00-00

Spot: SWNW

Sec/Twnshp/Rge: 28-24S-25E

1980 feet from N Section Line,

660 feet from W Section Line

Lease Name: LAFARGE

Well #: 1

County: BOURBON

Total Vertical Depth: 628 feet

Operator License No.: 8509

Op Name: EVANS ENERGY DEVELOPMENT, INC.

Address: 11 LEWIS DR.
PAOLA, KS 66071

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	6.25	20	0	

\$ 35.00

Well Type: DH

UIC Docket No:

Date/Time to Plug: 02/22/2006 3:00 PM

Plug Co. License No.: 8509

Plug Co. Name: EVANS ENERGY DEVELOPMENT, INC.

Proposal Rcvd. from: SCOTT EVANS

Company: EVANS ENERGY DEVELOPMENT, Phone: (913) 259-1203

Proposed
Plugging
Method:

THIS WELL CONSISTED OF AN UNCASD 5 5/8" BORE TO 628'. THE PLUGGING PROPOSAL WAS TO PLACE A 50' CEMENT PLUG AT T.D. AND TO PLACE A CONTINUOUS CEMENT PLUG FROM 250' TO SURFACE.

Plugging Proposal Received By: CLAYTON TITEL

WitnessType: NONE

Date/Time Plugging Completed: 03/22/2006 12:00 AM

KCC Agent: CLAYTON TITEL

Actual Plugging Report:

Perfs:

DRILL PIPE WAS RAN INTO THE WELL TO T.D.. 15 SACKS OF CEMENT WERE PUMPED THROUGH THE PIPE TO T.D.. THE PIPE WAS PULLED TO 250'. CEMENT WAS PUMPED INTO THE DRILL PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE DRILL PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

RECEIVED
KCC DISTRICT #3

MAR 29 2006 CPT

CHANUTE, KS

Remarks:

Plugged through: DP

District: 03

Signed

Clayton P. Titel

RECEIVED

(TECHNICIAN)

APR 03 2006

KCC WICHITA

INVOICED

DATE April 3, 06

20060411

PPT