

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-22391-00-00
Spot: W2NWNW Sec/Twnshp/Rge: 25-32S-4W
4678 feet from S Section Line, 5038 feet from E Section Line
Lease Name: EARLES Well #: 1
County: SUMNER Total Vertical Depth: 3070 feet

Operator License No.: 5039

Op Name: AGV CORP.

Address: 123 N. MAIN
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3054	810	
SURF	8.625	252	0	

\$ 99.78

Well Type: DH

UIC Docket No:

Date/Time to Plug: 03/08/2006 8:00 AM

Plug Co. License No.: 33204

Plug Co. Name: BASYE WELL SERVICE, INC.

Proposal Rcvd. from: LARRY G. MANS

Company: AGV CORP.

Phone: (620) 254-7222

Proposed Perfs 2046' - 2048'
Plugging CIBP above perfs & 2 sxs cmt
Method: 35 sxs @ 650'
circ cmt 300' - 0'

Plugging Proposal Received By: STEVE VANGIESON

WitnessType: PARTIAL

Date/Time Plugging Completed: 03/08/2006 5:00 PM

KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP was set at 1990' and capped with 2 sacks of cement. The casing was recovered from 810' and pulled to 650' where 35 sacks of cement were spotted. The casing was pulled to 317' where cement was circulated to 0'.

60/40 posmix with 4% gel

Allied Cement #16731

Perfs:

Top	Bot	Thru	Comments
2982	2988		SPF


RECEIVED
KCC DISTRICT #2
MAR 24 2006
WICHITA, KS

Remarks:

Plugged through: CSG

District: 02

Signed


(TECHNICIAN)

INVOICED
DATE April 4, 06
NO. 2006061454

RECEIVED
APR 04 2006
KCC WICHITA

Form CP-2/3

PCT