

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-22394-00-00
Spot: SWNE Sec/Twnshp/Rge: 26-32S-4W
3557 feet from S Section Line, 2079 feet from E Section Line
Lease Name: HASKINS Well #: A1
County: SUMNER Total Vertical Depth: 3087 feet

Operator License No.: 5039

Op Name: AGV CORP.

Address: 123 N. MAIN
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3083	0	
SURF	8.625	267	0	

\$100.33

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 03/01/2006 2:00 PM

Plug Co. License No.: 33204

Plug Co. Name: BASYE WELL SERVICE, INC.

Proposal Rcvd. from: LARRY MANNIS

Company: AGV CORP.

Phone: (620) 254-7222

Proposed
Plugging
Method:

Perfs @ 3001' - 3006'; set CIBP @ 2950' & cap w/ 2 sxs cmt; recover pipe to 650'; 35 sxs cmt @ 320'; circ cmt to 0'.

Plugging Proposal Received By: STEVE VANGIESON

WitnessType: PARTIAL

Date/Time Plugging Completed: 03/08/2006 4:25 PM

KCC Agent: STEVE VANGIESON

Actual Plugging Report:

3/1/2006
A CIBP was set at 2950' and capped with 2 sacks of cement. Shot casing off at 1847'. No recovery. Shot casing off at 1591'. No recovery. Shot casing off at 1031'. No recovery.

3/2/2006
Shot casing off at 734'. No recovery. Shot casing off at 680'. No recovery.

3/3/2006
Ran free point. Casing stuck at 320' - 330'.

3/6/2006
Perforated at 650'. Pumped 35 sacks of cement. Perforated at 285'. Cement did not circulate.

3/8/2006
Ran 1" tubing to 175' and circulated cement to 0'. Filled inside of 5-1/2" casing with cement.

60/40 posmix with 4% gel and 3% CC

Allied Cement

Perfs:

Top	Bot	Thru	Comments
3001	3006		SPF


**RECEIVED
KCC DISTRICT #2
MAR 21 2006
WICHITA, KS**

Remarks:

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)

INVOICED

4-4-06

DATE

2006061414

OR. NO.

RECEIVED

APR 04 2006

KCC WICHITA

Form CP-2/3

PCT