

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-20246-00-00
Spot: SESESE Sec/Twnshp/Rge: 23-19S-1W
329 feet from S Section Line, 437 feet from E Section Line
Lease Name: BRYAN Well #: 1
County: MCPHERSON Total Vertical Depth: 2948 feet

Operator License No.: 5736
Op Name: BRYAN, DOROTHY J.
Address: PO BOX 25
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2946		125 SX CMT
SURF	8.625	160		125 SX CMT

H 95.81

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/07/2006 9:00 AM
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.
Proposal Rcvd. from: LAMONTE P "BUD" DAVIS Company: SUNFLOWER WELL SERVICE, INC. Phone: (620) 628-4723

Proposed Sand back perfs to 2850'; cap w/ 4 sxs of cmt; circ cmt from 300' - 0'.
Plugging Method: 4-1/2" casing cemented on backside from 300' - 0'; no recovery.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: NONE
Date/Time Plugging Completed: 03/07/2006 10:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

The perforations were sanded back to 2850' and capped with 5 sacks of cement. 4-1/2" cemented on backside. No recovery. Loaded hole to 380'. Circulated cement from 380' - 0'.

60/40 posmix with 4% gel

Concrete Products #41176

Perfs:

Top	Bot	Thru	Comments
2908	2922		

**RECEIVED
KCC DISTRICT #2
MAR 24 2006
WICHITA, KS**

Remarks:

Plugged through: TBG

District: 02

Signed [Signature]
(TECHNICIAN)

INVOICE
DATE 4-4-06
INV. NO. 2006061415

**RECEIVED
APR 04 2006
KCC WICHITA**

PST