

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-21895-00-00  
Spot: SENWSW Sec/Twnshp/Rge: 2-19S-12W  
1650 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: MUSENBERG *U KCC PKT Well #: 1*  
*4-6-06 per operator*  
County: BARTON Total Vertical Depth: 3413 feet

Operator License No.: 3208  
Op Name: K & N PETROLEUM, INC.  
Address: 513 W. 6TH ST  
ELLINWOOD, KS 67526

| String | Size  | Depth (ft) | Pulled (ft) | Comment       |
|--------|-------|------------|-------------|---------------|
| PROD   | 5.5   | 3407       | 0           | w/100 sxs cmt |
| SURF   | 8.625 | 233        | 0           | w/170 sxs cmt |

*\$ 110<sup>92</sup>*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/16/2006 10:00 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: ED NEMNICH Company: K&N PETROLEUM, INC. Phone: (620) 564-3422

Proposed  
Plugging  
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/16/2006 12:00 PM KCC Agent: CASE MORRIS

**Actual Plugging Report:**

Perforated at 1450' and 675'.  
Ran tubing to 1515'.  
Circulated with 225 sxs 60/40 pozmix - 10% gel cement w/200# hulls.  
POOH. Tied onto casing and pumped 25 sxs cement.  
Max. P.S.I. 500#. S.I.P. 100#.  
Had circulation up backside for a while, then shut off.  
Vented slips in braden head. Could not pump down backside.

Perfs:

Remarks: COPELAND CEMENTING COMPANY.

Plugged through: CSG

**INVOICED**  
DATE 4-6-06  
2006061439

District: 04

*AD*

Signed

*Case Morris*

(TECHNICIAN)

MAR 27 2006

RECEIVED  
APR 06 2006  
KCC WICHITA

Form CP-2/3

*PKT*

