

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-23768-00-00
Spot: S2SWSW Sec/Twnshp/Rge: 14-19S-22W
330 feet from S Section Line, 660 feet from W Section Line
Lease Name: MARTIN Well #: 1
County: NESS Total Vertical Depth: 4360 feet

Operator License No.: 31086
Op Name: RICHLAN DRILLING, A GENERAL PAR
Address: 598 - 2ND AVE.
BEAVER, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comment
PC		1459		
PROD	5.5	4352	0	WITH 175 SX CMT
SURF	8.625	220		WITH 140 SX CMT

H. 141.70

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/29/2006 12:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: RICK SCHREIBER Company: RICHLAN DRILLING Phone: (620) 587-3224

Proposed Plugging Method: PUMP 300# HULLS - 45 SX CMT WITH 200# HULLS MIXED IN - 13 SX GEL SPACER TO 1500'. PUMP 125 SX CMT FROM 1500' - 0'. PRESSURE TEST. CHECK BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/29/2006 12:45 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

PUMP 300# HULLS - 45 SX CMT WITH 200# HULLS MIXED IN - 13 SX GEL SPACER TO 1500'. PUMP 125 SX CMT FROM 1500' TO 0'. PRESSURED TO 1400#. PUMP 15 SX CMT DOWN BACKSIDE. PRESSURED TO 400#.

Perfs:


Top	Bot	Thru	Comments
4350	4360	OH	

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: CSG

INVOICED
4-7-06
2006061451

District: 01



Signed Eric MacLaren
(TECHNICIAN)

RECEIVED
APR 07 2006
KCC WICHITA

[Handwritten signature]