

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-005-20111-00-00
Spot: E2W2SWNE Sec/Twnshp/Rge: 4-7S-21E
1948 feet from N Section Line, 2160 feet from E Section Line
Lease Name: WALNUT Well #: 4-1
County: ATCHISON Total Vertical Depth: 1525 feet

Operator License No.: 33233
Op Name: HEARTLAND OIL & GAS, INC.
Address: 1610 INDUSTRIAL PARK DRIVE
PAOLA, KS 66071

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	1516		144 SX CMT
SURF	8.625	224		98 SX CMT

\$ 49.50

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/24/2006 9:00 AM
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.
Proposal Rcvd. from: STEVE LITTELL Company: HEARTLAND OIL & GAS, INC. Phone: (913) 294-1400

Proposed Plugging Method: GEL FROM 1485' TO 1410' CEMTN FROM 1410' TO 1158', GEL FROM 1158' TO 175' CMT FROM 175' TO SURFACE.

Plugging Proposal Received By: TAYLOR HERMAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/24/2006 12:30 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

TAGGED BOTTOM AT 1470 FEET AND PUMPED 10 BARRELS OF GEL. GEL FROM 1470 FEET TO 1410 FEET. PULLED TUBING TO 1407 FEET AND PUMPED 35 SACKS OF GEL AND 30 SACKS OF CEMENT WITH 1 SACK OF COTTON SEED HULLS. DISPLACED WITH 6.5 BARRELS OF GELLED WATER. CEMENT FROM 1407 FEET TO 1145 FEET, GEL FROM 1145 FEET TO 284 FEET. PULLED TUBING TO 284 FEET AND CEMENTED WITH 35 SACKS OF CEMENT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
1358	1360		
1343	1344		
1287	1292		
1208	1209		

RECEIVED
KCC DISTRICT #3

APR 4 2006 TCH

CHANUTE, KS

RECEIVED
APR 10 2006
KCC WICHITA

INVOICED

4-10-06

2006061461

Remarks:

Plugged through: TBG

District: 03

Signed

Taylor C. Herman

(TECHNICIAN)

PG